

1 040421

5-12

49

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-22,310-00-00  
Approx. 80' N  
C NE NE, SEC. 7, T 30 S, R 13 W/E  
4700 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5506

Lease Name Tony Bell Well # 1

Operator: Woolsey Petroleum Corporation  
Name & Address: 107 North Market, Suite 600  
Wichita, KS 67202

County Barber 156.00  
Well Total Depth 4800 feet  
Conductor Pipe: Size 13 3/8 feet 100  
Surface Casing: Size 8 5/8 feet 1010

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Trans-Pac Drilling, Inc. License Number 5841

Address One Main Place, #410, Wichita, KS 67202

Company to plug at: Hour: 9 p.m. Day: 12 Month: 5 Year: 19 90

Plugging proposal received from Gary Pugh

(company name) Trans-Pac Drilling, Inc. (phone) 316-265-0226

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 764'-Top  
1st plug at 1020' with 50 sx cement, 2nd plug at 500' with 50 sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Stephen J. Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11 p.m. Day: 12 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1020' with 50 sx cement,

2nd plug at 500' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
5 15 90 MAY 15 1990  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED  
I (BY) observe this plugging.

DATE MAY 2 1990

Signed Stephen J. Pfeifer (TECHNICIAN)

WV. NO. 28713

5-12