

To: 1 031267
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-26

API NUMBER 15-007-22,436-00-00
C NW SW, SEC. 29, T. 7 S, R. 13 W
1980 feet from S section 11p
660 feet from WEX section 11p

TECHNICIAN'S PLUGGING REPORT

Operator License # 5506
Operator: Woolsey Petroleum Corp.
Name: _____
Address 107 N. Market, Ste. 600
Wichita, KS 67202-1807

Lease Name Edwin Lenkner Well # 1
County Barber
Well Total Depth 4845 157.46 ft.
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4" feet 214

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co., Inc. License Number 5929
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 1:30 a.m. Day: 26 Month: 3 Year: 19 94

Plugging proposal received from John Armbruster
(company name) Duke Drilling Co., Inc. (phone) 316-267-1331

purpose: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 860-870'
1st plug at 870' with 50 sx cement, 2nd plug at 240' with 60 sx cement,
3rd plug at 40' with 15 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:45 a.m. Day: 26 Month: 3 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 870' with 50 sx cement,
2nd plug at 240' with 60 sx cement,
3rd plug at 40' with 15 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 30 1994

Remarks: Used 60/40 Pozmix 6% gel by Allied.

CONSERVATION DIVISION
Wichita, Kansas

INVOICED (Additional description is necessary, use BACK of this form.)

I (XXXX / did not) observe this plugging.

DATE 4-6-94
INV. NO. 40232
3-26

Signed Steve Durrant
(TECHNICIAN)