

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20941-00-00
Spot: SENWNWSW Sec/Twnshp/Rge: 25-19S-33W
2293 feet from S Section Line, 4943 feet from E Section Line
Lease Name: VULGAMORE 1933 Well #: 1-25
County: SCOTT Total Vertical Depth: 5402 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4075		
CIBP		4500		
CIBP		4553		
CIBP		4600		
CIBP		4778		
CIBP		5050		
DVT		1805		WITH 350 SX CMT
PROD	5.5	5402	0	WITH 880 SX CMT
SURF	8.625	1436		WITH 500 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/19/2013 12:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: ANTHONY Company: TITAN WELL SERVICE Phone: (405) 429-5100

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 11/19/2013 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 170 SX CMT & 250# HULLS IN THE FIRST 30 SX CMT TO 2661'. DISPLACE WITH 24 BBLS OF WATER & PRESSURE TO 2000 PSI. TOC APPROX. 1000' INSIDE THE 5 1/2". TOC IN 5 1/2" X 8 5/8" ANNULUS APPROX. 500'. RAN SPLIT COLLAR SHOT AT 454'. CIRCULATE CMT TO SURFACE WITH 130 SX CMT. CASING & ANNULUS STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5100	5104		
4877	4884		
4817	4822		
4808	4812		
4796	4802		
4788	4792		
4724	4728		
4694	4702		
4648	4651		
4635	4637		
4627	4631		
4610	4618		
4558	4564		
4516	4550		
4094	4176		
2651	2661		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

RECEIVED

KCC WICHITA

DEC 12 2013

RECEIVED

District: 01

DEC 15 2013
KCC DOOR CITY

Signed

Ken Jehlik
12/20/2013

AWY