

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20941-00-00
Spot: SWNE Sec/Twnshp/Rge: 12-27S-6W
1980 feet from N Section Line, 1980 feet from E Section Line
Lease Name: SEIFERT Well #: 1
County: KINGMAN Total Vertical Depth: 4335 feet

Operator License No.: 6988
Op Name: SMITH, RICHARD E. DBA SMITH OIL O
Address: 410 N. ADAMS PO BOX 550
HUTCHINSON, KS 67504

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3003	2035	150 SX
SURF	8.625	291		225 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/30/2013 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: HUNTER CLARK Witness Type: PARTIAL
Date/Time Plugging Completed: 11/13/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 2748' CAPPED WITH 4 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2035' PULLED CASING TO 901' SPOTTED 35 SX CEMENT. WAITED 2 HOURS TAGGED TOC @ 745'. PULLED CASING TO 396' CIRCULATED TO SURFACE WITH 175 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
2808	2812		

KCC WICHITA
DEC 05 2013
RECEIVED

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, 60/40 4% POS MIX, TICKET #41924., PAST 10 TA - FOR NON USE.

Plugged through: CSG

District: 02

Signed BJ Hope
(TECHNICIAN)

✓ 12/20/2013