

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21264-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 21-19S-28W  
1590 feet from S Section Line, 933 feet from E Section Line  
Lease Name: MOWERY TRUST Well #: 1  
County: LANE Total Vertical Depth: 4720 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4625		WITH 2 SX CMT
PROD	5.5	4719	0	WITH 200 SX CMT
SURF	8.625	243		WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/19/2013 1:30 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: MORRIS SMITH Company: TRANS PACIFIC Phone: (316) 262-3596

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP GEL THEN 35 SX CMT & 150# HULLS. PULL TBG TO 2200' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/19/2013 4:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

\*\*BACKSIDE HAD 450 SX CMT PUMPED DOWN IT AFTER WELL WAS COMPLETED. RAN TEMPERATURE SURVEY & FOUND CMT DOWN TO 2200'.\*\*  
RUN TBG TO 4371' & PUMP 16 SX GEL, 35 SX CMT & 150# HULLS. PULLED TBG TO 2200' & MIXED 210 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 500#.

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

KCC WICHITA

DEC 04 2013

RECEIVED

District: 01

Signed Michael J. Maier  
(TECHNICIAN)

RECEIVED  
NOV 26 2013  
KCC DODGE CITY

✓12/20/2013

Form CP-2/3

*Handwritten initials*