

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22949-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 6-11S-18W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: PEAVEY Well #: 1-B
County: ELLIS Total Vertical Depth: 3580 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3579		200 SX
SURF	8.625	304		220 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/05/2013 1:30 PM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN B. Company: TRANS PACIFIC OIL CORP. Phone: (785) 483-1821

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement and 500 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/05/2013 6:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Perforations: 1700', 1375', 650' and 300'.
Got outside of pipe at 2900'.
Ran tubing to 2850' and pumped 125 sx cement w/300 # hulls. Pulled tubing to 1600' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 850' and pumped 75 sx cement. Cement circulated out backside. POOH. Hooked to casing and pumped 70 sx cement. Cement circulated out braden head. Shut in and pressured casing to 300 psi. Shut in.

GPS: 39.11870 -099.35974

Remarks: QUALITY CEMENTING TICKET # 7660

Plugged through: TBG

District: 04

Signed _____

Ray A. Dinkel

(TECHNICIAN)

CM

12/20/2013

KCC WICHITA

Form CP-2/3

DEC 16 2013

RECEIVED

DEC 10 2013