

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21589-00-00
Spot: S2NWNENE Sec/Twnshp/Rge: 19-25S-4W
445 feet from N Section Line, 990 feet from E Section Line
Lease Name: THALMANN Well #: 1-19
County: RENO Total Vertical Depth: 4110 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 200 W DOUGLAS AVE STE 520
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4104	2010	150 SX
SURF	8.625	224		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/05/2013 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 11/08/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

FLOWING BACK - HAD KILL WELL - 11/15/13., SET CIBP @ 3200' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2010' PULLED CASING TO 700' SPOTTED 35 SX CEMENT. TAGGED TOP OF CEMENT PLUG @ 580'. PULLED CASING TO 325' CIRCULATED TO SURFACE WITH 180 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3682	3690		
3663	3667		
3576	3616		
3560	3566		
3260	3682		

Remarks: QUALITY WELL SERVICE SUPPLIED CEMENT ALSO-CLASS A USED.

Plugged through: CSG

KCC WICHITA
DEC 05 2013
RECEIVED

District: 02

Signed BJ Hope
(TECHNICIAN)

12/20/2013

N