

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03212-00-00
Spot: NENENENE Sec/Twnshp/Rge: 14-15S-18W
4964 feet from S Section Line, 286 feet from E Section Line
Lease Name: DECHANT EAST Well #: 5
County: ELLIS Total Vertical Depth: 3602 feet

Operator License No.: 30259
Op Name: WERTH, ANDY DBA WERTH EXPLORA
Address: 1308 SCHWALLER AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	0		Partial liner depth unknown
PROD	5.5	3602		125 SX
SURF	8.625	1178		345 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/10/2013 1:45 PM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: ANDY WERTH Company: WERTH EXPLORATION TRUST Phone: (785) 625-4968

Proposed Plugging Method: Ordered 460 sx 60/40 pozmix 4% gel cement, 700 # hulls and 14 sx gel.
Alt i Completion. Well had multiple squeezes.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/11/2013 4:10 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Copeland rigged to 5 1/2" casing and mixed and pumped 50 sx cement w/150 # hulls followed by 13 sx gel followed by 325 sx cement w/550 # hulls mixed in. Well went on vacuum. Rigged to 8 5/8" casing and pumped 10 sx cement to pressure with 200 psi and 200 psi shut in pressure. Left well set over night.
12/11/2013-Topped off 5 1/2" casing with 75 sx cement. Hole standing full.

GPS: 38.75415 -099.28335
4973' FSL 275' FEL
SE NE NE NE


Perfs:

Remarks: COPELAND ACID AND CEMENTING TICKET # 41971

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

CM

DEC 12 2013

✓ 12/20/2013

KCC WICHITA

Form CP-2/3

DEC 17 2013

RECEIVED