

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25450-00-00  
Spot: SWNENENE Sec/Twnshp/Rge: 14-15S-18W  
4647 feet from S Section Line, 344 feet from E Section Line  
Lease Name: WERTH FAMILY Well #: 7-18  
County: ELLIS Total Vertical Depth: 3588 feet

Operator License No.: 30259  
Op Name: WERTH, ANDY DBA WERTH EXPLORA  
Address: 1308 SCHWALLER AVE  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	1953		420sx
PROD	5.5	3587		135sx
SURF	8.625	227		160 SX
TI	2.375	3584		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/10/2013 9:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: ANDY WERTH Company: WERTH EXPLORATION TRUST Phone: (785) 625-4968

Proposed Plugging Method: Ordered 285 sx 60/40 pozmix 4% gel cement, 14 sx gel and 500 # hulls.  
DV Tool at 1953' w/220 sx smd

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/10/2013 1:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Professional Pulling ran in hole to 3501'. Copeland rigged to tubing and mixed and pumped 14 sx gel followed by 50 sx cement w/150 # hulls mixed in. Pulled tubing to 1650. Mixed and pumped 175 sx cement w/150 # hulls to circulate cement to surface. Pulled tubing. Topped off 5 1/2" casing with 20 sx cement. Hole standing full. Rigged to 8 5/8" casing and pumped 20 sx cement w/200 psi and 200 psi shut in pressure.

GPS: 38.75326 -099.28356  
4649' FSL 330' FEL  
SW NE NE NE

Perfs:

Remarks: COPELAND ACID AND CEMENTING TICKET # 41970

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

KCC WICHITA

CM

DEC 12 2013

✓ 12/20/2013

DEC 17 2013

Form CP-2/3

RECEIVED