

1 030770

DEC 13 1987

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-22, 147-00-00

C NW SE, SEC. 14, T 31 S, R 10 W/E

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Rankin Well # 1

Operator: Hummon Corporation

County Barber 147.88

Name & Address 400 One Main Place

Well Total Depth 4550 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H-30 Drilling, Inc. License Number 5107

Address 251 N. Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 12 p.m. Day: 13 Month: 12 Year: 1986

Plugging proposal received from Rick Davis

(company name) H-30 Drilling, Inc. (phone) 316-793-3687

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 900' with 40 sx cement, 2nd plug at 280' with 50 sx cement,

3rd plug at 0-40' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2 p.m. Day: 13 Month: 12 Year: 1986

ACTUAL PLUGGING REPORT 1st plug at 900' with 50 sx cement,

2nd plug at 300' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION

JAN 5 1987

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

**INVOICED**

(If additional description is necessary, use BACK of this form.)

DATE 1-6-87

Signed Steve Durrant  
(TECHNICIAN)

INV. NO. 15801