

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20333-00-00
Spot: SWNESE Sec/Twnshp/Rge: 18-14S-28W
1650 feet from S Section Line, 990 feet from E Section Line
Lease Name: SMITH H Well #: 2
County: GOVE Total Vertical Depth: 4234 feet

Operator License No.: 33721
Op Name: MID-CON ENERGY OPERATING, INC.
Address: 2431 E 61ST ST STE 850
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4224		75 SX CMT
SURF	8.62	382		250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/26/2013 3:00 PM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: DAVIE MINYARD Company: CHEYENNED WELL SERVICE Phone: (405) 350-2012

Proposed Plugging Method: CIBP stuck at 2215'. Can not move it. Casing broken. CIBP at 3750'.
Ordered 450 sx 60/40 pozmix 4% gel cement and 500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/27/2013 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 380', 1175' and 2145'. Ran tubing to 2194' and pumped 450 sx cement w/250 # hulls. Lost circulation.
11/26/13- Pulled tubing out and shut down till next day.
11/27/13- Ran tubing back in and tagged cement at 990'. Pumped 105 sx cement. Good circulation of cement out casing. Closed casing in and pumped 80 sx cement with good circulation of cement out backside. Hole standing full.

GPS: 38.83425 -100.46850


Perfs:

Remarks: CONSOLIDATED CEMENT TICKET # 44442 AND 44536

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

✓ 12/20/2013

KCC WICHITA

Form CP-2/3

DEC 09 2013

RECEIVED

DEC 02 2013