

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-00685-00-01
Spot: SWNE Sec/Twnshp/Rge: 1-35S-35W
1973 feet from N Section Line, 1933 feet from E Section Line
Lease Name: ROTH Well #: 1-1
County: STEVENS Total Vertical Depth: 6800 feet

Operator License No.: 5263
Op Name: MIDWESTERN EXPLORATION COMPA
Address: 3500 S BOULEVARD STE 2B
EDMOND, OK 73013

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	2.875	6180		WITH 1/2 SX CMT
CIBP		6470		
PROD	5.5	6208	4000	WITH 250 SX CMT
SURF	8.625	1640		WITH 1000 SX CMT
T1	2.875	6653	4050	WITH 175 SX CMT

Well Type: DH UIC Docket No: Date/Time to Plug: 12/11/2013 9:30 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET 2 7/8" CIBP @ 6180' WITH 1/2 SX CMT. PLUG AT 1670' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/11/2013 2:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET 2 7/8" CIBP @ 6180' WITH 1/2 SX CMT. 1ST PLUG AT 1680' WITH 50 SX CMT.
2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6518	6522		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

KCC WICHITA

DEC 18 2013

RECEIVED

District: 01

RECEIVED

DEC 12 2013

KCC DODGE CITY

Signed

(TECHNICIAN)