

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-22188-00-00  
Spot: NENWSWE Sec/Twnshp/Rge: 14-28S-8W  
1095 feet from S Section Line, 2195 feet from E Section Line  
Lease Name: SIMONS Well #: 1  
County: KINGMAN Total Vertical Depth: 4119 feet

Operator License No.: 6236  
Op Name: MTM PETROLEUM, INC.  
Address: 2370 SOUTH STATE ROAD 14 PO BOX  
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		3690		
PROD	4.5	4107		125 SX
SURF	8.625	223		210 SX
T1	2.375	3720		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/15/2013 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 546-3032

Proposed Plugging Method: AS PRE KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/15/2013 3:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

TUBING STUCK IN CASING, SHOT TUBING OFF AT 3500' PUMPED 35 SX CEMENT TO COVER BOTTOM, PRESSURED UP TO 1500 LBS., DISPLACED TUBING TO 3500'. CUT TUBING @ 1232' AND PERFORATED CASING PUMPED 35 SX CEMENT. CUT TUBING AND PERFORATED CASING @ 750' PUMPED 35 SX CEMENT, RAN IN TAGGED TOC @ 940', PUMPED 20 SX CEMENT, LOCKED UP. RELEASED PRESSURE PULLED 31 JOINTS OF TUBING, THEN PERFORATED CASING AT 310', CIRCULATED TO SURFACE WITH 95 SX CEMENT, TOPPED OFF WITH ANOTHER 20 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4036	4042		
3756	3757		

KCC WICHITA

DEC 05 2013

RECEIVED

Remarks: QUALITY SUPPLIED CEMENT FOR JOB ALSO.

Plugged through: CSG

District: 02

Signed

*B. J. Hope*

(TECHNICIAN)

*12/20/2013*

*✓JK*