

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20521-00-00
Spot: NESWSWNW Sec/Twnshp/Rge: 6-10S-24W
3080 feet from S Section Line, 4810 feet from E Section Line
Lease Name: RIEDEL Well #: 1
County: GRAHAM Total Vertical Depth: 4085 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4084		125 SX
SURF	8.625	207		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2013 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSHNER Company: SWIFT Phone: (785) 567-8104

Proposed Plugging Method: Ordered 470 sx 60/40 pozmix 4% gel cement w/400 # hulls.
2 1/2" tubing stuck in casing at 3764'.

Plugging Proposal Received By: TOM CULLEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2013 2:00 PM KCC Agent: TOM CULLEY

Actual Plugging Report:

Ran tubing to 3748' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 2845' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 1696' and pumped 180 sx cement. Cement circulated. Pulled remaining tubing and connected to backside to pump 20 sx cement and pressure to 200 psi. Connected to casing and pumped 20 sx cement and pressured to 300 psi. Cellar began to fill with cement surrounding well head.

GPS: 39.21274 -100.05032

Perfs:

Top	Bot	Thru	Comments
4014	4018		
3972	3976		
3950	3954		
3852	3856		

Remarks: SWIFT TICKET # 25186

Plugged through: TBG

KCC WICHITA

DEC 09 2013

RECEIVED

District: 04

Signed _____

Tom Culley
(TECHNICIAN)

CM

NOV 20 2013

✓ 12/20/2013