

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-05721-00-00
Spot: SESWSE Sec/Twnshp/Rge: 9-15S-12W
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: ZEMAN B Well #: 2
County: RUSSELL Total Vertical Depth: 3263 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3248		125 SX
SURF	8.625	480		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2013 11:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GREG Company: MURFIN DRILLING CO., INC. Phone: (785) 483-5371

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 13 sx gel and 300 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/20/2013 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1250', 725' and 350'. Ran tubing to 3150' and pumped 13 sx gel followed by 50 sx cement w/50 # hulls. Pulled tubing to 1280' and pumped 125 sx cement. Cement circulated out back side. POOH. Hooked to casing and pumped 15 sx cement at 400 psi. Shut in. Found the well was squeezed at 625' w/175 sx cement.

GPS: 38.75590 -098.65735

Perfs:

Top	Bot	Thru	Comments
3248	3263		

Remarks: QUALITY CEMENTING TICKET # 7015

Plugged through: TBG

District: 04

Signed Ray A Dinkel
(TECHNICIAN)

CM

✓ 12/20/2013

KCC WICHITA

Form CP-2/3

DEC 04 2013

RECEIVED