

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-05723-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 9-15S-12W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: ZEMAN - B Well #: 4
County: RUSSELL Total Vertical Depth: 3289 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3182		
PROD	5.5	3276		125 SX
SURF	8.625	500		275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/19/2013 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GREG Company: MURFIN DRILLING CO., INC. Phone: (785) 483-5371

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 9 sx gel and 300 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2013 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 350', 725' and 1250'. Pulled 101 joints out of well leaving 3 joints. Mud anchor, tubing anchor and seating nipple. Ran tubing to 2950' and pumped 9 sx gel followed by 75 sx cement w/100 # hulls. Pulled tubing to 1250' and pumped 175 sx cement. Cement circulated out back side. POOH. Hooked to casing and pumped 95 sx cement. Cement circulated out braden head. Shut in valve on braden head and pressured to 200 psi. Shut in casing.

GPS: 38.75773 -098.66001

Perfs:

Top	Bot	Thru	Comments
3160	3164		
3069	3082		
3052	3058		
3012	3022		

Remarks: QUALITY CEMENTING TICKET # 7242

Plugged through: TBG

District: 04

Signed Ray Dinkel

(TECHNICIAN)

KCC WICHITA

CM

12/20/2013

DEC 04 2013

Form CP-2/3

RECEIVED

NOV 25 2013