

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20997-00-00
Spot: SENWNWSE Sec/Twnshp/Rge: 22-17S-34W
2150 feet from S Section Line, 2245 feet from E Section Line
Lease Name: NIGHTENGALE Well #: 2
County: SCOTT Total Vertical Depth: 4910 feet

Operator License No.: 31900
Op Name: NOR-WEST KANSAS OIL, L.L.C.
Address: 20014 283 HWY
WAKEENEY, KS 67672

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	259		WITH 175 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/21/2013 3:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: MARK BIGGE Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2400' WITH 50 SX CMT. 2ND PLUG AT 1380' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 290' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 11/21/2013 6:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 2400' WITH 50 SX CMT. 2ND PLUG AT 1380' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 290' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL /4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

District: 01

Signed



(TECHNICIAN)

RECEIVED
DEC - 7 2013
KCC WICHITA

12/20/2013

KCC WICHITA

Form CP-2/3

DEC 09 2013

RECEIVED