

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20391-00-01  
Spot: NWNESW Sec/Twnshp/Rge: 25-29S-33W  
2316 feet from S Section Line, 1674 feet from W Section Line  
Lease Name: DANIELS Well #: 2-25  
County: HASKELL Total Vertical Depth: 5800 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4625		WITH 2 SX CMT
CIBP		5324		WITH 2 SX CMT
PROD	4.5	5505	2643	WITH 300 SX CMT
SURF	8.625	1635		WITH 605 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/15/2013 8:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 5324' WITH 2-5 SX CMT. CIBP @ 4625' WITH 2-5 SX CMT. PLUG AT 1665' WITH 10-15 SX GEL & 50 SX CMT. PLUG AT 700' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: DANIEL SELLERS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/15/2013 12:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CIBP @ 5324' WITH 2 SX CMT. CIBP @ 4625' WITH 2 SX CMT. 1ST PLUG AT 1683' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 719' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5374	5384		MORROW
4675	4676		KANSAS CITY B

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

(TECHNICIAN)

KCC WICHITA

RECEIVED

DEC - 3 2013

KCC DODGE CITY

12/20/2013

DEC 09 2013

RECEIVED

Form CP-2/3