

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-20526-00-00
Spot: SESESENW Sec/Twnshp/Rge: 21-24S-36W
2590 feet from N Section Line, 2440 feet from W Section Line
Lease Name: BURDEN A Well #: 2
County: KEARNY Total Vertical Depth: 2960 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2959	726	WITH 225 SX CMT
SURF	8.625	671		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/06/2013 11:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 25 SX CMT WITH 300# HULLS. TAG WITH WIRELINE. PLUG AT 2100' WITH 25 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/07/2013 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TAG FL @ 2500'. TAG PBTB @ 2900'. PUMP 300# HULLS & 50 SX CMT ON BOTTOM.
TAG TOC WITH SINKER BAR @ 1380' AFTER 24 HOURS. PLUG AT 714' WITH 50 SX
CMT. PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2751	2758		
2713	2724		
2670	2688		

Remarks: **COMPLIANCE ISSUE: HIGH FL** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG


KCC WICHITA

DEC 04 2013

RECEIVED

District: 01

Signed



(TECHNICIAN)

RECEIVED

NOV 20 2013

KCC DODGE CITY

12/20/2013

ADP