

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21982-00-00
Spot: W2NENESW Sec/Twnshp/Rge: 20-27S-33W
2310 feet from S Section Line, 2269 feet from W Section Line
Lease Name: KELLS G Well #: 1
County: HASKELL Total Vertical Depth: 5769 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5761	2214	WITH 295 SX CMT
SURF	8.625	1779		WITH 580 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2013 11:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT TO PLUG PERFS. LOAD WITH MUD. PLUG AT 1810' WITH 50 SX CMT. PLUG AT 900' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2013 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 200# HULLS & 25 SX CMT TO 5244'. PRESSURE TO 1500#. HOLDING. 1ST PLUG AT 1810' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5234	5244		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

KCC WICHITA

DEC 04 2013

RECEIVED

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

✓ 12/20/2013

RECEIVED

NOV 20 2013

KCC DODGE CITY

AM