

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20448-00-00
Spot: NESWNESE Sec/Twnshp/Rge: 25-26S-27W
1827 feet from S Section Line, 819 feet from E Section Line
Lease Name: CIRCLE D Well #: 25-9
County: GRAY Total Vertical Depth: 5650 feet

Operator License No.: 34848
Op Name: POLLOK ENERGY, LLC
Address: 501 N. 4TH PO BOX 106
PURCELL, OK 73080

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	86		
SURF	8.625	1419		WITH 800 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/25/2013 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVID HICKMAN Company: POLLOCK ENERGY Phone: (405) 527-6038

Proposed Plugging Method: 1ST PLUG AT 1710' WITH 50 SX CMT. 2ND PLUG AT 1450' WITH 50 SX CMT. 3RD PLUG AT 900' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/25/2013 2:30 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

Perfs:

LOADED HOLE WITH MUD. 1ST PLUG AT 1705' WITH 50 SX CMT. 2ND PLUG AT 1457' WITH 50 SX CMT. 3RD PLUG AT 899' WITH 50 SX CMT. 4TH PLUG AT 62' WITH 50 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed

Nathan Willis

(TECHNICIAN)

RECEIVED

DEC - 3 2013

KCC DODGE CITY

12/20/2013

KCC WICHITA

DEC 09 2013

RECEIVED

Form CP-2/3

AM