

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20389-00-01
Spot: E2NWNWNE Sec/Twnshp/Rge: 31-11S-22W
330 feet from N Section Line, 2190 feet from E Section Line
Lease Name: SPENA Well #: 1
County: TREGO Total Vertical Depth: 4063 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3909		150 SX
SURF	8.625	133		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/08/2013 9:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: THOMAS ATKINS Company: ULTIMATE WELL SERVICE, LLC Phone: (785) 216-0155

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement and 600 # hulls

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/08/2013 3:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perforations: 3792' - 3799', 3775' - 3783', 3690' - 3693', 3659' - 3662'. Shot perforation at 125', 1800', 1000' and 2350'.
Ran tubing to 3690' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 3200' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1850' and pumped 200 sx cement w/350 # hulls. Good circulation of cement. Pulled tubing out. Topped off casing w/35 sx cement. Tied on to backside and squeezed w/60 sx cement. Hole standing full.

GPS: 39.05833 -099.80485

Perfs:


Top	Bot	Thru	Comments
3775	3783		
3691	3694		
3690	3693		
3660	3663		
3659	3662		
3493	3800		
3492	3799		

Remarks: CONSOLIDATED CEMENT TICKET # 44460

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

Form CP-2/3

DEC 09 2013

RECEIVED

✓ 12/20/2013

DEC 09 2013