

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-14476-00-00  
Spot: N2NWNE Sec/Twnshp/Rge: 1-20S-12W  
4950 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: WOLF B Well #: 3  
County: BARTON Total Vertical Depth: 3362 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3071		
PROD	5.5	3331		125 SX
SURF	8.625	310		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/15/2013 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: SCOTT BOEH Company: RITCHIE EXPLORATION Phone: (620) 617-4671

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 500 # hulls and 7 sx gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/15/2013 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1500', 550' and 300'. Ran tubing to 3050 and pumped 7 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1550' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 550'. Circulated cement to surface with 190 sx cement. Pulled tubing and topped off with 50 sx cement. Backside full. Ciculated cement to surface.

GPS: 38.34713 -098.59749

Perfs:

Top	Bot	Thru	Comments
3237	3245		
3213	3215		
3163	3164		
3144	3146		
3119	3137		
3087	3101		
3078	3080		

Remarks: ALLIED CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

NOV 25 2013

✓ 12/20/2013

KCC WICHITA

Form CP-2/3

DEC 04 2013

RECEIVED