

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-21609-00-01  
Spot: SWSWNWSW Sec/Twnshp/Rge: 10-31S-20W  
1570 feet from S Section Line, 240 feet from W Section Line  
Lease Name: LUKE Well #: 1-10  
County: COMANCHE Total Vertical Depth: 5205 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4900		WITH 2 SX CMT
CIBP		5000		WITH 2 SX CMT
CIBP		5205		
CIBP		5550		
COND		90		WITH 12 SX CMT
PROD	7.625	6160	940	WITH 250 SX CMT
SURF	10.75	906		750 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/11/2013 1:00 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: JESSICA TRIPP Company: SANDRIDGE EXPLORATION Phone: (405) 429-5500

Proposed Plugging Method: SET CIBP @ 4900' WITH 2 SX CMT. SET CIBP @ 5000' WITH 2 SX CMT. PLUG AT 930' WITH 15 SX GEL & 80 SX CMT. PLUG AT 400' WITH 80 SX CMT. PLUG AT 60' WITH 40 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/11/2013 3:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4900' WITH 2 SX CMT. SET CIBP @ 5000' WITH 2 SX CMT. RAN TBG TO 918'. CIRCULATED HOLE WITH MUD. 1ST PLUG AT 918' WITH 80 SX CMT. DISPLACED WITH 4 BBL MUD. 2ND PLUG AT 409' WITH 80 SX CM. DISPLACED WITH 1 BBL WATER. 3RD PLUG AT 60' WITH 25 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5613	5797		
5217	5221		
5056	5156		
4952	4958		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

KCC WICHITA

DEC 18 2013

RECEIVED

District: 01

RECEIVED

DEC 13 2013

KCC DODGE CITY

Signed

*Eric MacLaren*

(TECHNICIAN)

✓ 12/20/2013

AWZ