

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-203-20246-00-00  
Spot: SENWNWNE Sec/Twnshp/Rge: 12-17S-36W  
400 feet from N Section Line, 2240 feet from E Section Line  
Lease Name: SIMONS 1736 Well #: 1-12  
County: WICHITA Total Vertical Depth: 5050 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	9.625	1519		WITH 740 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/26/2013 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: CODY CONALLIS Company: SANDRIDGE Phone: (405) 429-5500

Proposed Plugging Method: 1ST PLUG AT 2400' WITH 60 SX CMT. 2ND PLUG AT 1550' WITH 75 SX CMT. 3RD PLUG AT 900' WITH 75 SX CMT. 4TH PLUG AT 60' WITH 30 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE  
Date/Time Plugging Completed: 11/26/2013 1:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 2400' WITH 60 SX CMT. 2ND PLUG AT 1550' WITH 75 SX CMT. 3RD PLUG AT 900' WITH 75 SX CMT. 4TH PLUG AT 60' WITH 30 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
DEC - 9 2013  
KCC DODGE CITY

12/20/2013

KCC WICHITA

Form CP-2/3

DEC 12 2013

RECEIVED