

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20945-00-00
Spot: NWSESE Sec/Twnshp/Rge: 2-18S-33W
430 feet from S Section Line, 335 feet from E Section Line
Lease Name: SIMPSON 1833 Well #: 1-2
County: SCOTT Total Vertical Depth: 5475 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4200		WITH 5 SX CMT
CIBP		4410		
CIBP		4615		
CIBP		4705		
CIBP		4735		
CIBP		5170		
PROD	5.5	5475	715	WITH 675 SX CMT
SURF	8.625	1459		WITH 500 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/21/2013 12:00 PM
Plug Co. License No.: 34982 Plug Co. Name: TITAN WELL SERVICE, LLC
Proposal Rcvd. from: ANTHONY Company: TITAN WELL SERVICE, LLC Phone: (405) 828-4225

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 11/21/2013 9:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4200' WITH 5 SX CMT. CIRCULATE HOLE WITH MUD. RAN SPLIT COLLAR SHOT AT 2235'. ATTEMPT TO PULL CASING @ 80000#. COULD NOT PULL CASING. SET CMT RETAINER @ 2135'. SPOT 50 SX CMT AT 2278' @ 2 BPM @ 500#. 30 SX CMT OUTSIDE 5 1/2" & 20 SX CMT INSIDE THE 5 1/2". PERFORATE @ 1510'. SPOT 50 SX CMT. MUD CIRCULATED OUT ANNULUS. CUT 5 1/2" CASING @ 715'. RUN TBG TO 655' & SPOT 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5209	5263		
4747	4788		
4710	4729		
4640	4682		
4455	4466		
4250	4262		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

KCC WICHITA

DEC 12 2013

RECEIVED

District: 01

RECEIVED

DEC - 8 2013

KCC DODGE CITY

Signed

Ken Jehlik
12/20/2013

(TECHNICIAN)

AM