

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20971-00-00  
Spot: NESWSWNW Sec/Twnshp/Rge: 35-16S-31W  
3088 feet from S Section Line, 4861 feet from E Section Line  
Lease Name: SOWERS 1631 Well #: 1-35  
County: SCOTT Total Vertical Depth: 5260 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3900		WITH 5 SX CMT
PROD	5.5	5260	1340	WITH 415 SX CMT
SURF	8.625	2077		WITH 675 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/26/2013 11:00 AM  
Plug Co. License No.: 34982 Plug Co. Name: TITAN WELL SERVICE, LLC  
Proposal Rcvd. from: ANTHONY Company: TITAN WELL SERVICE, LLC Phone: (405) 828-4225

Proposed Plugging Method: CIBP @ 3900' WITH 2 SX CMT. PLUG AT 1350' WITH 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/26/2013 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 3900' WITH 5 SX CMT. 1ST PLUG AT 2250' IN 5 1/2" CASING WITH 25 SX CMT. 2ND PLUG AT 1332' IN 8 5/8" CASING WITH 50 SX CMT. 3RD PLUG AT 747' IN 8 5/8" CASING WITH 50 SX CMT. 4TH PLUG AT 60' IN 8 5/8" CASING WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4144	4152		
4103	4109		
4031	4038		
3994	3998		
3950	3956		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED

DEC - 3 2013

KCC DODGE CITY

11/20/2013

KCC WICHITA

DEC 12 2013

RECEIVED

Form CP-2/3

RAM