

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barber County. Sec. 25 Twp. 34S Rge. 13 E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
C/SE SW

Lease Owner Andover Oil Company  
Lease Name Blanche Sterling Estate Well No. 1

Office Address 4545 One Williams Center, Tulsa, Ok  
Character of Well (Completed as Oil, Gas or Dry Hole) oil


Date Well completed 12-31-76 19  
Application for plugging filed 10-17-78 19  
Application for plugging approved 10-25-78 19  
Plugging commenced 2-2-79 19  
Plugging completed 2-7-79 19

Reason for abandonment of well or producing formation uneconomical

If a producing well is abandoned, date of last production 1-8-77 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Owen  
Producing formation Miss. Chat Depth to top 4896 Bottom 4912 Total Depth of Well 4970  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Beds	water	0	213	8 5/8"	213	none
Mississippi Chat	oil & gas	0	4969	4 1/2"	4969	3631

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Ran wire line measurement and found top of fill-up at 4773 (123' of fill above perfs). Dumped 4 sks of regular neat cement at 4773' with dump bailer. Plug #1 @ 4773-4730'. Shot off 4 1/2" casing at 3631' and pulled out of hole. Mixed 5 sks of hulls and 18 sks of gel and pumped down 8 5/8" casing followed by 100 sks of 60/40 Poz-Mix containing 2% gel, and 3% CaCl<sub>2</sub> and filled casing. Cut casing off 3' below ground level and welded on steel plate.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pullers

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_ ss.

\_\_\_\_\_, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *RW Boltz*

(Address) \_\_\_\_\_ 1979

Subscribed and sworn to before me this 28th day of February

My Commission Expires June 27, 1982

*June Carol Reed*  
Notary Public.


RECEIVED  
STATE CORPORATION COMMISSION

MAR - 5 1979

CONSERVATION DIVISION  
Wichita, Kansas

# WELL LOG

COMPANY Sands Drilling Company SEC. 25 T. 34S R. 13W  
14W  
 FARM Sterling Estate 4B. 1 LOC. 660 FSL 1980 FWL  
 TOTAL DEPTH 4970' COUNTY Barber  
 COMM. 4-29-75 COMP. 5-15-75  
 CONTRACTOR DaMac Drilling Company, Inc.



CASING  
 8 5/8 casing set @ 213

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

20	568	Red Bed
568	1545	Shale
1545	1930	Shale & Lime
2095	2335	Lime
2335	4626	Lime & Shale
4626	4680	Lime
4680	4725	Lime & Shale
4725	4970	Lime
	4970	RTD

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 OCT 25 1978  
 CONSERVATION DIVISION  
 Wichita, Kansas

State of Kansas  
 County of Barton

I, Martha J. McKown of DaMac Drilling Company, Inc.

do hereby state the above and foregoing is a true and correct copy of the log of the Sterling Estate No. 1 well.

DONALD SLOUP  
 STATE NOTARY PUBLIC  
 Barton County, Kansas  
 My Commission Expires  
 November 11, 1978

Subscribed and sworn to before me this 17 day of June, 19 75

My Commission Expires: Nov. 11, 1978

Martha J. McKown  
Donald Sloup  
NOTARY PUBLIC