

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 25 TWP. 34S RGE. 13W E/W
Location as in quarters or footage from lines:
N/2 NE NW

Locate Well
correctly on above
Section Platt.

Lease Owner Pickrell Drilling Company
Lease Name Allen Well No. E1
Office Address 205 Litwin Building, 110 N. Market, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole): Dry
Date Well Completed 4-25-81
Application for plugging filed 5-28-81
Plugging commenced 7-22-81
Plugging completed 7-28-81 11:30
Reason for abandonment of well or producing formation Dry

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Barnett

Producing formation _____ Depth to top _____ bottom _____ T.D. 4930

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	245	None
				4 1/2	4927	3980

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set. Plug back at 4868

Dumped in sand - from 4868 to 4800

Dumped 4 sacks cement with dump bailer from 4800 to 4770

Ripped pipe at 4100 4030 3980

Built bridge at 280' rock from 280' 270'

5 yards ready mix to surface

RECEIVED
STATE CORPORATION COMMISSION

JUL 31 1981

(If additional description is necessary, use BACK of this sheet) CONSERVATION DIVISION
Name of Plugging Contractor Clarke Corporation Wichita, Kansas

STATE OF Kansas COUNTY OF Barber, ss.
Elmo R. Mergenslern (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Elmo R. Mergenslern
Medicine Lodge, Mo.
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of July, 1981

Jessie Hamilton
Notary Public.

My Commission expires: April 4 1982

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
205 Litwin Building, 110 North Market
Wichita, Kansas 67202
Rotary Drilling Commenced 4-14-81
Rotary Drilling Completed 4-25-81
LOCATION: #1 Allen 'E'
N/2 NE NW, Sec. 25-34S-13W
Barber County, Kansas
CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Spud 4-14-81, surface pipe 8 5/8", depth 245' KB, cem 150 sx, comp 4-14-81.
Ran 126 jts 4 1/2" 10.5# csg, set & cem at 4927 w/150 sx common w/L.C. mtl.
Plug dwn 10:30 a.m. on 4-26-81.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Top Soil	40
Red Beds	248
Shale	1425
Shale & Lime	2020
Lime & Shale	4755
Lime	4930

RECEIVED
STATE CORPORATION COMMISSION
JUN -4 1981
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 3rd day of June, 1981, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires:

December 9, 1982
JANA LEA SCHNEWEIS
STATE NOTARY PUBLIC
Sedgwick County, Kansas

[Signature]
Notary Public
Jana Lea Schneewis