

15-007-20095-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 10 Twp. 21S Rge. (E) 11 (W)
Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner Tilco, et al
Lease Name Bergner Well No. 1
Office Address 815 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-27 1969
Application for plugging filed 4-27 1969
Application for plugging approved 4-27 1969
Plugging commenced 4-27 1969
Plugging completed 4-27 1969
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation Depth to top Bottom Total Depth of Well 4892 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	208'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug with 1/2 sack hulls and 25 sacks cement filled hole to 40' with mud. Set plug with 1/2 sack hulls and 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
MAY 5 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 1969

My commission expires

April 1, 1971

Ulansa Nichols
Notary Public.

DRILLER'S LOG

COMPANY	Tilco, et al
CONTRACTOR	LEBEN DRILLING, INC.
FARM	BERGNER #1
LOCATION	C NE SW SECTION 10-31S-11W BARBER COUNTY, KANSAS
COMMENCED	4-14-69
COMPLETED	4-27-69

0	135	Sand, Clay
135	191	Red Bed
191	210	Red Bed, Shale
210	1250	Shale
1250	1800	Shale, Lime
1800	2150	Lime
2150	2545	Lime, Shale
2545	2781	Lime
2781	2975	Lime, Shale
2975	3300	Lime
3300	3630	Lime, Shale
3630	3885	Shale, Lime
3885	4658	Lime
4658	4721	Shale, Lime
4721	4815	Lime
4815	4838	Cherty Lime
4838	4892	Lime
	<u>4892</u>	<u>RTD - D. & A.</u>

RECEIVED
STATE CORPORATION COMMISSION
5-5-69
MAY 5 1969
CONSERVATION DIVISION
Wichita, Kansas

8 5/8" 20# new surface casing set @ 208.46' cemented with 225 sacks Sunset cement

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Bergner #1 Well located C NE SW of Section 10, Township 31 South, Range 11 West, Barber County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
Leslie Kite

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 2nd day of May, 1969.

Ulanda Nichols
Ulanda Nichols

My Commission Expires:
April 1, 1971