


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Barber County. Sec. 9 Twp. 31 Rge. 11 (X) (W)  
Location as "NE/CNW/SW" or footage from lines NE NW SE  
Lease Owner Musgrove Petroleum Corporation  
Lease Name Smith "B" Well No. 1  
Office Address 518 Petroleum Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed June 21, 19 53  
Application for plugging filed June 23, 19 53  
Application for plugging approved. 19  
Plugging commenced June 21, 19 53  
Plugging completed June 21, 19 53  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Unknown  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4883 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	308'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud. Set surface plug at 300' with 20 sacks of cement.  
Second plug at 40' with 10 sacks of cement.

RECEIVED  
CONSERVATION DIVISION  
6-24-53  
JUN 24 1953

(If additional description is necessary, use BACK of this sheet.)  
Name of Plugging Contractor Musgrove Petroleum Corporation  
Address 518 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling  
518 Petroleum Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 1953

Mary S. Dunn  
Notary Public.

My commission expires Nov. 14, 1956

PLUGGING  
FILE SEC. 9 T. 31 R. 11W  
BOOK PAGE 109 LINE 28

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation  
 CONTRACTOR: Musgrove Petroleum Corporation  
 FARM: Smith "B" # 1  
 LOCATION: NE NW SE. Section 9-31-11  
 Barber County, Kansas

COMMENCED: May 26, 1953  
 COMPLETED: June 21, 1953

0	75	Surface clay
75	175	Clay and sand
175	273	Red bed
273	500	Shale
500	690	Red bed
690	980	Red bed and shale
980	1420	Shale
1420	1600	Shale and shells
1600	1645	Lime
1645	1740	Shale
1740	2300	Lime and shale
2300	2380	Brown lime
2380	3221	Lime and shale
3221	3338	Lime
3338	3850	Lime and shale
3850	3966	Sand
3966	4017	Sand and lime
4017	4416	Lime
4416	4468	Lime and shale
4468	4500	Lime
4500	4524	Lime and chert
4524	4536	Mississippi
4536	4547	Lime and shale
4547	4590	Mississippi lime
4590	4650	Lime and shale
4650	4791	Shale
4791	4865	Viola
4865	4883	Simpson
	4883	Rotary Total Depth

Set 8 5/8" surface casing at 308' with 250 sacks of cement.

Dry and abandoned;

**RECEIVED**  
 STATE CORPORATION COMMISSION

STATE OF KANSAS )

COUNTY OF SEDGWICK )

SS

JUN 24 1953  
 6-24-53  
 CONSERVATION DIVISION  
 Wichita, Kansas

**PLUGGING**  
 FILE SEC 9 T 31 R 11W  
 BOOK PAGE 109 LINE 28

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the Smith "B" # 1 NE NW SE Section 9-31-11 Barber County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling  
 Secretary-Treasurer

Subscribed and sworn to before me a Notary Public in and for Sedgwick County, Kansas, this 23rd day of June, 1953.

Mary L. Quinn  
 Notary Public