

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 5 Twp. 31S Rge. 11 ~~EX~~W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE NE NE


Lease Owner Smith-Fancher
Lease Name Axline Well No. 5-1
Office Address 650 - 17th Street, Suite 508, Denver, Colo. 80202
Character of Well (Completed as Oil, Gas or Dry Hole): _____

Dry Hole
Date Well completed June 22, 1979
Application for plugging filed June 22, 1979
Application for plugging approved June 22, 1979
Plugging commenced June 22, 1979
Plugging completed June 22, 1979
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3920
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	236'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 240 feet. Pumped 40 sacks cement through drill pipe with pump truck. Pushed plug and 1/2 sack hulls to 40' and pumped 12 sacks of cement through drill pipe with pump truck to base of well cellar. Plugged rat hole with 3 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

III - 3 1979

7-3-79

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Betty Brandt (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Betty Brandt
910 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 1979

Rebecca L. Matthews
Rebecca L. Matthews Notary Public.

My commission expires May 17, 1983

ROTARY DRILLERS' LOG

OPERATOR: Smith-Fancher DRILLING COMMENCED: June 16, 1979
650 - 17th Street, Suite 508
Denver, Colorado 80202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: June 22, 1979
910 Union Center
Wichita, Kansas 67202

CASING RECORD: 5 Jts. 236' new 8-5/8" 24# cemented with 225 sacks. LOCATION: Axline No. 5-1
NE NE **NE**
Section 5-31S-11W
Barber County, Kansas

0 - 130 Sand & clay
130 - 1220 Red bed
1220 - 1775 Red bed & shale
1775 - 3740 Shale & lime
3740 - 3840 Sand & shale
3840 - 3920 Shale & sand
3920 Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Becca P. Smith
Secretary-Treasurer

RECEIVED
STATE CORPORATION COMMISSION

JUL - 3 1979
7-3-79
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)
) ss.
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 2nd day of July, 1979.

Rebecca L. Matthews
Rebecca L. Matthews Notary Public

My commission expires: May 17, 1983