


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

HARPER County. Sec. 15 Twp. 35S Rge. (E) 6 (W)

Location as "NE/CNW/SW" or footage from lines C NW NW
Lease Owner PARLAY OIL COMPANY
Lease Name SAPPHIRE Well No. 1
Office Address P. O. Box 14371, OKLAHOMA CITY, OKLAHOMA
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed JAN. 6, 1968
Application for plugging filed (PHONE 1/6/68) JAN. 10, 1968
Application for plugging approved JAN. 6, 1968
Plugging commenced JAN. 6, 1968
Plugging completed JAN. 6, 1968
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING
Producing formation Depth to top Bottom Total Depth of Well 4070 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	249'	8-5/8"	249'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 240 FEET. SET FIRST PLUG WITH 1/2 SACK HULLS, 1 SACK DRY CEMENT, 24 SACKS CEMENT @ 240 FEET. FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET SECOND PLUG @ 40 FEET WITH 1/2 SACK HULLS, 1 SACK DRY CEMENT, 9 SACKS CEMENT. PLUGGED RAT HOLE WITH 2 SACKS CEMENT. JOB STARTED 8:30 PM ON 1/6/68 AND JOB COMPLETED 10:00 PM ON 1/6/68.

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor GABBERT-JONES, INC.
Address 830 SUTTON PLACE, WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. E. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall
830 SUTTON PLACE, WICHITA, KANSAS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of JANUARY, 1968

Barbara J. Layton
BARBARA J. LAYTON Notary Public.



MY COMMISSION EXPIRES FEB. 1, 1968

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

SAPPHIRE #1
 C NW NW SECTION 15-35S-6W
 HARPER COUNTY, KANSAS

COMMENCED: DECEMBER 23, 1967
 COMPLETED: JANUARY 7, 1968

OPERATOR - PARLAY OIL COMPANY

DEPTH		FORMATION	REMARKS
From	To		
0	150	RED BED	
150	249	RED ROCK, SAND AND SHALE	RAN 13 JOINTS 8-5/8" CASING, SET @ 249' W/225 SACKS CEMENT.
249	1150	SHALE	
1150	1480	LIME AND SHALE	
1480	2010	LIME	
2010	3645	LIME AND SHALE	
3645	3724	SHALE	
3724	3790	SAND AND SHALE	
3790	3860	LIME	
3860	3995	LIME AND SHALE	
3995	4070	LIME	
4070	TD		DRY AND ABANDONED.

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 11 1968
 CONSERVATION DIVISION
 Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C NW NW SECTION 15-35S-6W, HARPER COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 9TH DAY OF JANUARY, 1968, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

My COMMISSION EXPIRES FEBRUARY 1, 1968.

