

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
206 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-20817-00-00

LEASE NAME Tohm

WELL NUMBER C-1

SPOT LOCATION \_\_\_\_\_

SEC. 36 TWP. 30S RGE. 12 ~~XX~~ or (W)

COUNTY Barber

Date Well Completed 12-31-79

Plugging Commenced 2-19-86

Plugging Completed 2-21-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR TXO Production Corp.

ADDRESS 200 West Douglas, Suite #300 Wichita, Ks. 67202

PHONE # (316) 265-9441 OPERATORS LICENSE NO. 5171

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.

Is AC0-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Mississippian Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4275'  
19' open hole  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	253'	10 3/4	253'	0
		253'	4256'	4 1/2	4003	75 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Dumped 325 sx. cement in 10 3/4, 175 sx. cement in 4 1/2 csg. Filled 70' csg. with 96 gallons of sand. Top of sand at 4120'.

2-19-86 Rugged up. 2-20-86 Pulled rods and tubing, dumped 135 gallons of sand.

2-21-86 Dumped 4 sx. cmt., cut 4 1/2 and pulled 75 jts. of casing.

TOP HOLE PLUGGING: 2 hulls, 15 gel, 50 sx. cement, 10 gel, 1 hulls, 8 5/8 plug, 180 sx. cement.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893  
Address Box 847 Pratt, Ks. 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (employee of ~~operator~~ plugging contractor)  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Box 847 Pratt, Ks.



SUBSCRIBED AND SWORN TO before me this 11 day of March, 1986

REC'D Dorothy M. Furgason  
STATE CORPORATION COMMISSION Notary Public

My Commission expires February 6, 1989

MAR 12 1986

CONSERVATION DIVISION