

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 36 Twp. 30S Rge. (X) 12 (W)

Location as "NE/CNW/SW" or footage from lines: C NE NE  
Lease Owner Dunne-Gardner Drilling Co., Inc.  
Lease Name Thom Well No. 1  
Office Address 300 Schweiter Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed January 25, 19 65  
Application for plugging filed January 29, 19 65  
Application for plugging approved 19  
Plugging commenced January 25, 19 65  
Plugging completed January 25, 19 65  
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation Depth to top Bottom Total Depth of Well 4419 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		-0-	210	8-5/8"	1-12-65	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 220', set plug with 1/4 sack hulls and 25 sacks cement. Mud to 40', set plug with 1/4 sack hulls and 10 sacks cement. 25 sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 1 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor  
Address

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Don Gardner (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
300 Schweiter Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of January, 19 65

[Signature]  
Marilyn E. Fox  
Notary Public.

My commission expires November 9, 1965

9

DRILLER'S LOG

OPERATOR: Dunne-Gardner Drilling Co., Inc.  
300 Schweiter Building, Wichita, Kansas

CONTRACTOR: Dunne-Gardner Drilling Co., Inc.

LEASE: Thom

WELL: No. 1

LOCATION: C NE NE Section 36-30S-12W

DATE COMMENCED: January 12, 1965

DATE COMPLETED: January 25, 1965

CASING: Set 8-5/8" surface pipe at 210' w/200 sacks cement

<u>FROM</u>	<u>TO</u>	
0	210	Sand and Clay
210	905	Red Bed and Shale
905	1430	Red Bed, Shale and Shells
1430	1735	Shale and Gypsum
1735	1875	Lime and Shale
1875	1990	Lime
1990	2103	Lime and Shale
2103	2240	Lime and Shale Streaks
2240	2465	Lime
2465	2610	Lime and Shale Streaks
2610	3527	Shale and Lime
3527	3540	Sand
3540	3650	Sand, Lime and Shale
3650	3825	Lime and Shale
3825	3843	Sand
3843	3887	Lime
3887	3954	Lime and Shale
3954	4419	Lime

R. T. D.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 1 1965

CONSERVATION DIVISION  
Wichita, Kansas


I certify the above to be true and correct to the best of my knowledge and belief.

DUNNE-GARDNER DRILLING CO., INC.

By   
Dan Gardner

Subscribed and sworn to before me this 29th day of January, 1965.

My Commission Expires:  
November 9, 1965

  
Marilyn E. Fox, Notary Public