

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-007-01020-00-02

API NUMBER Drilled-1946

LEASE NAME Wulf Ranch

WELL NUMBER A-2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 19 TWP. 30 SW SW SE RGE. 11 (X) or (W)

COUNTY Barber

Date Well Completed 1946

Plugging Commenced 11-22-89

Plugging Completed 1-9-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR American Intermountain Development Corp.

ADDRESS P.O. Box 664 Layton, Utah 84041

PHONE# (801) 546-1382 OPERATORS LICENSE NO. 8129

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-29-89 and 1-9-90 (date)

by Morris and Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4540

Show depth and thickness of all water, oil and gas formations. Perfs: 4428-38

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	240	8 5/8	240	0
				4 1/2		2474' 60 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
11-22-89: Pulled and layed down rods and tubing, dumped 150 sx. of sand.
11-28-89: Top of sand 4346', dumped 4 sx. cement, shot off 4 1/2 at 2474'. Pulled 60
jts. 12-1-90: 300# hulls, 10 gel, 50 sx. 10 gel, 100# hulls, 8 5/8 plug, 100 sx. 60
40- poz, 6% gel (see back of Page)
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893

Address P. O. Box 847 Pratt, Kansas 67124


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Intermountain Development Corp.

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (Employee of ~~XXXXXXXXXXXXXXXXXXXX~~ plugging contractor)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above-described well, as filed the
the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) P.O. Box Pratt, Ks.



SUBSCRIBED AND SWORN TO before me this 11th day of January, 19 90

Dorothy M. Ferguson
Notary Public

My Commission Expires: February 6, 1993

Jan. 9, 1990: Took rig to location, rigged up and ran in hole with 160' of tubing. Circulated hole clean and were on solid cement. Pulled tubing and bit out of the hole, took off the bit and ran back in. BJ Titan cement with 40 sx. Pulled out of the hole, rigged down and moved off. Steve Durant on location.

