

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Barber County, Sec. 16 Twp. 30S Rge. 11 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines Apx C SE  
Lease Owner Barnett Oil Company  
Lease Name Thom Well No. 1  
Office Address 411 First National Bank Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed July 24, 1971  
Application for plugging filed July 24, 1971  
Application for plugging approved July 24, 1971  
Plugging commenced July 24, 1971  
Plugging completed July 24, 1971  
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4723 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	268.85'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged hole w/ 1/2 sx Hulls &  
Plug @ 265' & 35 sx cement - Mud  
to 40', 1/2 sx Hulls & Plug w/10 sx  
cement to surface, Plugged Rathole  
w/2 sx cement. Hole plugged @ 3:15 P.M.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 5 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company  
Address 1720 Wichita Plaza, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Jim Farrice (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Farrice  
1720 Wichita Plaza, Wichita, Kansas  
(Address)



October 25, 1972

Notary Public.

DRILLERS LOG

No. 1 Thom

CASING RECORD:

8 5/8" @ 275'  
w/275 sx cement

COMPANY:

Barnett Oil Company

DESCRIPTION:

CONTRACTOR:

Red Tiger Drilling Company

Apx. C SE

COMMENCED:

July 11, 1971

16-30S-11W

COMPLETED:

July 24, 1971

Barber County,  
Kansas

TOTAL DEPTH: 4723'

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Clay	0	165	
Red Bed	165	585	
Shale	585	1720	
Lime & Shale	1720	1755	
Lime	1755	2375	
Lime & Shale	2375	3885	
Lime	3885	4390	
Lime, Chert, Shale	4390	4525	
Lime	4525	4595	
Shale, Lime w/Chert	4595	4697	
Lime w/Chert	4697	4723	

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 5 1971  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Fausse

Subscribed and sworn to before me this 28th day of July, 1971.



Gloria Fawcett  
Notary Public

My Commission Expires:

October 25, 1972