

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ness County. Sec. 9 Twp. 20 Rge. (E)21 (W)

Location as "NE/CNW%SW%" or footage from lines C NW SE

Lease Owner Pickrell Drilling Company

Lease Name Betz Estate Well No. 2

Office Address 705 4th National Bank Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 4, 19 64

Application for plugging filed December 4, 19 64

Application for plugging approved December 4, 19 64


Plugging commenced December 4, 19 64

Plugging completed December 4, 19 64

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4490 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	501	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 500 feet, set plug, cemented with 25 sacks cement.
Heavy mud to 180 feet, set plug, cemented with 20 sacks cement.
Heavy mud to 40 feet, set plug, cemented with 10 sacks cement to
bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
12-10-64
DEC 10 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PICKRELL DRILLING COMPANY
Address See Above

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. SEBITS (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
C. W. Sebitts
705 4th National Bank Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of December, 1964

My commission expires June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public.

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Bldg
Wichita, Kansas

Rotary Drilling Commenced 11-22-64

Rotary Drilling Completed 12--4-64

LOCATION: Betz Estate No. 2, C NW SE Section 9-20-21W, Ness County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (24 jts) 8 5/8" surface casing set at 501' cemented with 225 sacks cement. Circulated. Completed 10:45 P.M. November 22, 1964.
No oil string run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

60	Top Soil & Clay	<u>C. F. S.</u>
125	Shale	4362
430	Shale & Shells	4420
465	Sandy Shale	4425
650	Shale	4430
835	Red Beds & Shale	4435
845	Blaine	4440
935	Shale & Shells	4450
1135	Sand	4454
1490	Shale, Shells & Red Beds	4459
1520	Anhydrite	
2210	Shale & Shells	
2250	Shale & Lime Streaks	<u>Slope Tests</u>
2535	Lime & Shale	2500
2740	Lime	3025
3465	Lime & Shale	3575
3630	Shale & Lime & Sand	4105
3755	Shale & Lime	
4260	Lime	
4420	Lime & Shale	<u>S. L. M.</u>
4434	Conglomerate	3559
4490	Mississippian - RTD	4013
		4297

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1964

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 9th day of December, 19 64, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public