


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Harper County, Sec. 12 Twp. 35S Rge. 7 (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW/4 SW/4  
Lease Owner National Cooperative Refinery Association  
Lease Name Kathryn Meyer Well No. 1  
Office Address 305 Rule Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 31, 1961  
Application for plugging filed March 30, 1961  
Application for plugging approved March 30, 1961  
Plugging commenced March 31, 1961  
Plugging completed March 31, 1961  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5393 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	258'	None-Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded hole to 240 feet, dumped 1/4 sack hulls plus 15 sacks of cement.

Mudded hole to 35 feet, dumped 1/4 sack hulls plus 10 sacks of cement on up to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

APR 11 1961

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Leben Drilling, Inc.  
Address 905 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. R. Sears (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.R. Sears (C. R. Sears)

305 Rule Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of April, 1961

My commission expires November 26, 1964

Nell McComb Notary Public.



DRILLER'S LOG

COMPANY:  
 CONTRACTOR:  
 FARM:  
 LOCATION:  
 COMMENCED:  
 COMPLETED:

NATIONAL COOPERATIVE REFINERY ASSOCIATION  
 LEBEN DRILLING, INC.  
 Meyer #1  
 C SW SW, Sec. 12-35S-7W  
 Harper County, Kansas  
 3-11-61  
 3-31-61

0	100	Shale
100	250	Shale and shells
250	258	Shale
258	675	Red Bed
675	870	Shale and red bed
870	910	Anhydrite
910	1295	Shale and shells
1295	1545	Shale and shells
1545	1740	Shale and lime
1740	1935	Lime
1935	2075	Lime
2075	2300	Lime and shale
2300	2600	Lime and shale
2600	2765	Lime
2765	2970	Lime and shale
2970	3100	Lime
3100	3265	Lime
3265	3358	Lime
3358	3381	Elgin
3381	3500	Lime
3500	3620	Lime
3620	3662	Lime
3662	3840	Lime
3840	3975	Lime
3975	4023	Lime
4023	4061	Lime
4061	4078	Lime
4078	4245	Lime
4245	4265	Lime
4265	4312	Kansas City Lime
4312	4425	Lime
4425	4480	Lime
4480	4590	Lime
4590	4655	Lime
4655	4690	Lime
4690	4759	Lime
4759	4795	Lime
4795	4831	Lime
4831	4855	Mississippi Lime
4855	4870	Mississippi Lime
4870	4895	Mississippi Lime
4895	4919	Mississippi Lime
4919	4955	Mississippi Lime
4955	4980	Mississippi Lime
4980	5005	Mississippi Lime
5005	5024	Mississippi Lime
5024	5050	Mississippi Lime
5050	5066	Mississippi Lime
5066	5102	Mississippi Lime
5102	5133	Mississippi Lime
5133	5159	Mississippi Lime
5159	5184	Mississippi Lime
5184	5211	Mississippi Lime
5211	5223	Mississippi Lime
5223	5305	Shale and lime
5305	5338	Shale and lime
5338	5355	Lime
5355	5373	Lime
5373	5380	Simpson Sand
5380	5393	Simpson Sand
5393	5397	Simpson Sand

**RECEIVED**  
 STATE CORPORATION COMMISSION

APR 11 1961

CONSERVATION DIVISION  
 Wichita, Kansas

Driller's Log - #1 Meyer, C SW SW, Sec. 12-35S-7W, Harper County, Kansas

5397 Rotary Total Depth

Set 8 5/8" surface casing at 258' with 200 sacks Quick set.

I, Theodore I. Leben, do hereby certify that the above and foregoing is a true and correct copy of the log of the Meyer #1, located C SW SW, of Section 12, Township 35S, Range 7W, Harper County, Kansas, as reflected by the files of Leben Drilling, Inc.

Theodore I. Leben  
Theodore I. Leben

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS.

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 10th day of April, 1961.

Ruth N. Benjamin  
Ruth N. Benjamin, Notary Public

My commission expires:

June 17, 1961

*Enbrook*