


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Harper County, Sec. 6 Twp. 35 Rge. (E) 7 (W)  
Location as "NE/CNW/SW" or footage from lines SE SW NW  
Lease Owner Continental Oil Company  
Lease Name F. H. McKee Well No. 1  
Office Address Box 161, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-25 19 55  
Application for plugging filed 5-25 19 55  
Application for plugging approved 5-25 19 55  
Plugging commenced 5-25 19 55  
Plugging completed 5-25 19 55  
Reason for abandonment of well or producing formation no commercial shows

If a producing well is abandoned, date of last production -- 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation none Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	oil	4765	4780	10 3/4	239	none
Mississippi	water	4900	4915			
Simpson	water	5300	5318			
Simpson	gas & oil	5347	5362			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 220' and dumped 25 sacks cement.  
Mudded up to 15' and capped with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 3 - 1955

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor G-M-R Drilling Company  
Address Box 1033, Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
F. L. Dunn (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

ARC-DCS  
5-31-55

State RFD REL File

(Signature) [Signature]  
Box 161, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of May, 1955

My commission expires Dec. 4, 1958 [Signature] Notary Public.

PLUGGING  
FILE SEC 6 T 35 R 7W  
BOOK PAGE 123 LINE 1

WELL RECORD

Location: SE SW NW, 6-35S-7W  
Harper County, Kansas

Commenced: May 5, 1955

Operator: Continental Oil Company  
335 West Lewis, Wichita, Kansas

Completed: May 26, 1955

Contractor: Graham-Messman-Rinehart Drilling Co.  
1005 East Second, Wichita, Kansas

Elevation:

Production: Dry

Casing Record: 10 3/4" @ 239' w/250 sacks cement

.....L O G.....

Clay-Sand	40
Red Bed	239
Shale	280
Shale-Lime	1978
Lime-Shale	2127
Shale-Lime	2427
Lime-Shale	2615
Shale-Lime	3020
Lime-Shale	3200
Shale-Lime	3535
Lime-Shale	3678
Shale-Sandy Lime	3947
Lime-Shale	4047
Shale	4154
Shale-Lime	4213
Lime	4672
Shale	4753
Lime-Chert	4944
Lime	5107
Lime-Shale	5148
Shale	5179
Shale-Lime	5261
Lime	5305
Lime-Sand	5318
Sand	5420
Shale	5491
Arbuckle	5518 R.T.D.

The undersigned, GRAHAM-MESSMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART DRILLING COMPANY

By:


*J. A. Gilliland*  
J. A. Gilliland

Subscribed and sworn to before me  
this 9th day of June 1955.

*Juanita L. Davis*  
Notary Public

My Commission Expires: November 5, 1958

SCC RFD SRC FLD



RECEIVED  
STATE CORPORATION COMMISSION  
JUN 15 1955  
CONSERVATION DIVISION  
Wichita, Kansas