


15-007-20637-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County. Sec. 8 Twp. 30 Rge. 11W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
1550' FEL & 1900' FNL of NE/4
Lease Owner Kruckenber and Scott
Lease Name Coss Well No. 1
Office Address Isabel, Kansas 67065
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole
Date Well completed July 5, 1978
Application for plugging filed Verbal Application 19____
Application for plugging approved Verbal Approval 19____
Plugging commenced July 5, 1978
Plugging completed July 5, 1978
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____
19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,927'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>JUL 1 1978</u>				<u>8-5/8"</u>	<u>243'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,927 ft. (rotary total depth) to 480 ft. Set plug at 480 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 480 ft. to 240 ft. Set plug at 240 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 240 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 12 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg. Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (Signature of owner) ~~XXXXXXXXXXXXXXXXXXXX~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)



My commission expires June 30, 1982 before me this 10th day of July, 19 78

Elsie Willison
Elsie Willison - Notary Public.

KANSAS DRILLERS LOG

COMPANY **Kruckenber and Scott**

SEC. **8** T. **30** R. **11W**
LOC. **1550' FEL & 1900' PNL**
of **NE/4**

FARM **Coss**

NO. **1**

COUNTY **Barber**

ROTARY TOTAL DEPTH **3,927'**
COMM. **June 28, 1978**
CONTRACTOR **H-30, Inc.**
ISSUED **July 10, 1978**

COMP. **July 5, 1978**

CASING

10 3/4"
8 5/8" **Set at 243' cemented w/200 sxs cement**
5 1/2"
4 1/2"

ELEVATION **1,845 K.B.**

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	190'
Red Bed and Shale	375'
Shale	510'
Shale and Lime	550'
Shale	1,557'
Shale and Lime	1,760'
Lime and Shale	3,880'
Lime	3,927'
Rotary Total Depth	3,927'

RECEIVED
STATE CORPORATION COMMISSION
JUL 11 1978
CONSERVATION DIVISION
Topeka, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 10th day of July, 1978.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

June 30, 1982