


15-007-00030-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 14 Twp. 32 Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines: C NE NE
Lease Owner: Stelbar Oil Corporation, Inc.
Lease Name: Stewart Well No. 1
Office Address: 310 Petroleum Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole): dry hole
Date well completed: April 22, 19 61
Application for plugging filed: April 22, 19 61
Application for plugging approved: April 22, 19 61
Plugging commenced: April 22, 19 61
Plugging completed: April 22, 19 61
Reason for abandonment of well or producing formation: dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well: Fred W. Hampel
Producing formation: Depth to top: Bottom: Total Depth of Well 4460 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	214'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with mud to 210', set plug and dumped 15 sacks cement, filled with mud to 35', set plug and dumped 10 sacks cement, two sacks in rat hole, steel plate welded on surface.

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1961
4-27-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Stelbar Oil Corporation, Inc.
Address: 310 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bertrand M. Lester, Jr., (employee of owner) or (XXXXXX) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bertrand M. Lester, Jr.
310 Petroleum Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26 day of April, 19 61

My commission expires January 18, 1964

Leona Hargrove
Notary Public.

LOG

Farm: Stewart
Well No. 1
C NE NE 14-32-11W
Barber County, Kansas

Owner: Stelbar Oil Corporation, Inc.
Contractor: Stelbar Oil Corp., Inc.
Drilling Commenced: 4-7-61
Drilling Completed: 4-22-61

8-5/8" 214' cemented with 175 sacks

Elevation: 1526 DF

0	20	Sand
20	214	Red rock and shells
214	1575	Red rock and shale
1575	1616	Lime
1616	3240	Shale and Lime
3240	3290	Shale, sandy
3290	3605	Shale and Lime
3605	3621	Sand
3621	3726	Sand and shale
3726	3753	Shale
3753	4337	Lime
4337	4425	Lime and shale
4425	4460	Mississippi Lime
4460		Total Depth, D & A

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1961
4-27-61
CONSERVATION DIVISION
Wichita, Kansas

Filled with mud to 210', set plug and dumped 15 sacks cement, filled with mud to 35', set plug and dumped 10 sacks cement, two sacks in rat hole, steel plate welded on surface.