

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-077-21,034-00-00

LEASE NAME Hanna Rucker

WELL NUMBER 1-24

SPOT LOCATION NW NW SE

SEC. 24 TWP. 34 SRGE. 9 ~~10~~ (W)

COUNTY Harper

Date Well Completed 10-9-84

11:30 PM,

Plugging Commenced 10-8-84

12:45 AM,

Plugging Completed 10-9-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F. G. Holl

6427 East Kellogg

ADDRESS Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 50567

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 2

Is ACO-1 filed?                      If not, is well log attached? Yes

Producing formation                      Depth to top                      bottom                      T.D. 4950'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	258'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud. 35 sacks at 1500'; 35 sacks at 300';  
25 sacks at 60'. 10 sacks in rathole; 10 sacks in mousehole;  
5 sacks in water well. Used 60/40 Pozmix, 2% gel and 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142  
Address P. O. Box 129, Sterling, Kansas 67579 STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF RICE, ss.

OCT 18 1984

F. A. Wuellner (employee of operator) Wichita, Kansas  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STERLING DRILLING COMPANY  
(Signature) F. A. Wuellner  
F. A. Wuellner, Secretary  
(Address) P. O. Box 129, Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 10 day of October, 19 84

Agnes D. Wurst  
Agnes D. Wurst, Notary Public



My Commission expires: 4-6-85

# STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- HANNA RUCKER #1-24

Located: C NW NW SE, Section 24-34S-9W, Harper County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 29, 1984

COMPLETED: October 9, 1984

TOTAL DEPTH: 4950'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 40 Red Bed and Sand	Ran 6 joints new 8 5/8" OD casing.
40 - 257 Red Bed	243.24' pipe set at 258' K.B.
257 - 1035 Shale	Cemented with 200 sacks Class A, 2% gel and 3% cc. Plug down at 10:15 PM, 9-29-84, by Howco.
1035 - 1565 Shale and Lime Stringers	
1565 - 3556 Lime and Shale	
3556 - 3625 Douglas Sand	
3625 - 4950 Lime and Shale	Plugged.

Deviation Surveys: 1 1/4° at 1605'  
1° at 3625'