

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-00617-00-02  
Spot: SWSWNE Sec/Twnshp/Rge: 29-34S-5E  
3035 feet from S Section Line, 2480 feet from E Section Line  
Lease Name: BOGGS Well #: 1  
County: COWLEY Total Vertical Depth: 2767 feet

Operator License No.: 7466  
Op Name: BRADLEY & BRADLEY OIL, A GENERA  
Address: PO BOX 124  
DEXTER, KS 67038

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	120		CEMENTED 231'-0'
PROD	5.5	2767		toc 2200'

Well Type: EOR UIC Docket No: E24445.1 Date/Time to Plug: 10/25/2011 8:00 AM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3060

Proposed Plugging Method: AS PER KCC PER RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/25/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2600', CONSOLIDATED MIXED & PUMPED 50 SXS CLASS A COMMON 2% CC AND DISPLACED IN CASING. TAGGED CEMENT @2177'. SHOT SQUEEZE HOLES @ 260'-261'. RIH W/TBG @ 260', CONSOLIDATED ESTABLISHED CIRCUALTION AND MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 10/25/2011, 5:00 PM. CONSOLIDATED CEMENT TICKET #31691.

Perfs:

Top	Bot	Thru	Comments
2701	2724	CSG	

RECEIVED  
NOV 10 2011  
KCC WICHITA

Remarks: COMPLIANCE/FAILED MIT

Plugged through: TBG

District: 02

Signed

Duane Krueger  
(TECHNICIAN)

cc to MIC 11/14/11  
11/15/11  
Form CP-2/3