

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-019-19387-00-00  
Spot: NWNESENV Sec/Twnshp/Rge: 15-34S-12E  
3770 feet from S Section Line, 3234 feet from E Section Line  
Lease Name: WINDERS Well #: 6  
County: CHAUTAUQUA Total Vertical Depth: 1060 feet

Operator License No.: 32619  
Op Name: EXCEL OIL & GAS L.L.C.  
Address: PO BOX 68  
BUCYRUS, KS 66013

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10	20		
PROD	6	1060		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/02/2011 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Revd. from: MATT JONES Company: \_\_\_\_\_ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement and production casing cement unknown.  
Run 1" to TD. Gel hole. Spot 20 sacks of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and plug with 20 sacks at 700'.  
Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE  
Date/Time Plugging Completed 08/03/2011 11:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1000' gelled hole and spotted 20 sack plug. Pulled 1" and perforated the well at 700' and 350'. Ran 1" back into 700' and spotted 20 sack plug. Pulled up to 350' and circulated cement to surface. A total of 154 sacks of cement were used to plug this well.

RECEIVED

NOV 3 2011 DAS

KCC Chanute Dist. #3

RECEIVED  
NOV 14 2011  
11-14-11  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

11/16/11