

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19383-00-00

Spot: NENESENW

Sec/Twnshp/Rge: 15-34S-12E

3672 feet from S Section Line, 2654 feet from E Section Line

Lease Name: WINDERS

Well #: 1

County: CHAUTAUQUA

Total Vertical Depth: 1060 feet

Operator License No.: 32619

Op Name: EXCEL OIL & GAS L.L.C.

Address: PO BOX 68

BUCYRUS, KS 66013

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comment</u>
SURF	10	20		
PROD	6	1060		

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/04/2011 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: MATT JONES

Company:

Phone: (620) 725-3636

Proposed Plugging Method: This is an old shot hole well found abandoned in the field and appears to be a pre-1967 vintage. No data is available for this well from KCC. We intend to plug it as per the direction of District 3 office of KCC. Please assign API number as you may deem appropriate. The well number was assigned by us. Thanks

Plugging Proposal Received By: DUANE SIMS

Witness Type: PARTIAL

Date/Time Plugging Completed 08/05/2011 10:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1000' gelled hole and spotted 20 sack plug. Pulled 1" out and perforated at 700' and 350'. Came back next day. Ran 1" to 700' spotted 20 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 165 sacks of cement were used to plug this well.

RECEIVED

NOV 3 2011 DAS

KCC Chanute Dist. #3

RECEIVED

NOV 14 2011


KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)