

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19384-00-00
Spot: SWNESENW Sec/Twnshp/Rge: 15-34S-12E
3557 feet from S Section Line, 3050 feet from E Section Line
Lease Name: WINDERS Well #: 3
County: CHAUTAUQUA Total Vertical Depth: 1060 feet

Operator License No.: 32619
Op Name: EXCEL OIL & GAS L.L.C.
Address: PO BOX 68
BUCYRUS, KS 66013

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10	20		
PROD	6	1060		

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/01/2011 12:00 AM

Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: MATT JONES Company: Phone: (620) 725-3636

Proposed Surface cement and production casing cement unknown.
Plugging Run 1" to TD. Gel hole. Spot 20 sacks of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and
Method: plug with 20 sacks at 700'.
Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS

WitnessType: PARTIAL

Date/Time Plugging Completed 08/02/2011 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1000' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 700' and 350'. Next day ran 1" to 700' and spotted 20 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 200 sacks of cement were used to plug this well.

RECEIVED
NOV 3 2011
KCC Chanute Dist. #3

RECEIVED
NOV 14 2011
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed D. A. L.
(TECHNICIAN)