

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19386-00-00

Spot: SESENNW

Sec/Twnshp/Rge: 15-34S-12E

4225 feet from S Section Line, 2920 feet from E Section Line

Lease Name: WINDERS

Well #: 5

County: CHAUTAUQUA

Total Vertical Depth: 1060 feet

Operator License No.: 32619

Op Name: EXCEL OIL & GAS L.L.C.

Address: PO BOX 68
BUCYRUS, KS 66013

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10	20		
PROD	6	1060		

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/08/2011 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: MATT JONES

Company:

Phone: (620) 725-3636

Proposed Plugging Method: Surface cement and production casing cement unknown.
Run 1" to TD. Gel hole. Spot 20 sacks of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and plug with 20 sacks at 700'.
Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS

WitnessType: NONE

Date/Time Plugging Completed 08/09/2010 8:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1000' gelled hole and spotted 20 sacks. Pulled 1" and perforated well at 700' and 350'. Ran back into 700' and spotted 20 sack plug. Pulled up to 350' and circulated cement to surface. A total of 160 sacks of cement were used to plug this well.

RECEIVED

NOV 3 2011

KCC Chanute Dist. #3

DAS

RECEIVED

NOV 14 2011

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)