

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-27051-00-00
Spot: SESWNW Sec/Twnshp/Rge: 24-32S-10E
2310 feet from N Section Line, 990 feet from W Section Line
Lease Name: FLOYD 'A' Well #: 32
County: CHAUTAUQUA Total Vertical Depth: 2100 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	135		80 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/28/2011 12:00 AM
Plug Co. License No.: 6044 Plug Co. Name: STELBAR OIL CORPORATION, INC.
Proposal Rcvd. from: ROSCOE L. MENDENHALL Company: _____ Phone: (316) 264-8378

Proposed Plugging Method: PLUG WELL W/ 205 SKS. CEMENT AS FOLLOWS: 15 SKS. @ 2100'; 15 SKS. @ 1500'; 160 SKS. FROM 500' TO SURFACE; 15 SKS. IN RATHOLE. ALL CEMENT WAS 60/40 POZMIX W/ 4% GEL.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed 07/28/2011 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Pulled through drill pipe. At 2100' gelled hole and 15 sack plug. Pulled up to 1500' and spotted 15 sack plug. Pulled up to 500' and circulated cement to surface. Pulled drill pipe and topped well off. Also put 15 sacks in rat hole. A total of 205 sacks of 60/40 poz mix was used to plug this well.

RECEIVED

NOV 8 2011 DAS

KCC Chanute Dist. #3

RECEIVED
NOV 14 2011
KCC WICHITA

Remarks:

Plugged through: DP

District: 03

Signed



(TECHNICIAN)