

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-24985-00-00
Spot: NWNESWSE Sec/Twnshp/Rge: 32-33S-12E
1120 feet from S Section Line, 1670 feet from E Section Line
Lease Name: TROTTER Well #: 7 AX
County: CHAUTAUQUA Total Vertical Depth: 1018 feet

Operator License No.: 31471
Op Name: ROBERTS, RANDY
Address: 1122 RD 23
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40		8 SX
PROD	4.5	1018		110 SX

Well Type: EOR] UIC Docket No: E24231.1 Date/Time to Plug: 09/06/2011 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: RANDY ROBERTS Company: Phone: (620) 725-5229

Proposed Plugging Method: RUN 1" TO TD. GEL HOLE. SPOT 20 SX OF CEMENT OF BOTTOM. PULL UP AND SPOT 20 SX @ 700'. PULL UP TO 350' AND CEMENT TO SURFACE

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 09/07/2011 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Washed 1" to 1000' gelled hole and spotted 5 sack plug. Pulled up to 700' and spotted 5 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 2" and topped well off. A total of 42 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
946	958		WAYSIDE

RECEIVED
NOV 14 2011
KCC WICHITA

RECEIVED
NOV 3 2011 DAS
KCC Chanute Dist. #3

Remarks: PLUGGED BECAUSE WELL WOULD NOT PASS MIT

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)

[Handwritten notes]
Form CP-2/3
10/16/11